



Definitions Page:

**Approvals required for Building Permits:**

Sewer Test:	Sewer lines installed and pressure tested by contractor.
TV Video OK:	Closed circuit television inspection of sewer mains by contractor.
Water Test:	Water lines installed, pressure and bacteria tested by contractor.
Temp St. Signs:	All weather street signs, same size and height as permanent.
Road Base:	ACHD approved base, not necessarily paved yet.
Address:	Recorded plat has been received and addresses have been assigned.
PZ Approval:	Perimeter fencing (at least the orange construction containment fence with bonding for permanent), landscaping and/or bonding. Other items as required by council approval.
Special:	Any items specifically required by the City of Meridian as part of a development agreement.

**Approvals required for Certificates of Occupancy:**

Water Final:	Water system has received final approval by the City of Meridian.
Sewer Final:	Sewer system has received final approval by the City of Meridian.
Record Dwg:	<a href="#">Link to Submittal Requirements for Record Drawings</a>
Perm St. Signs:	Permanent street signs installed.
Street Lights:	All streetlights required are installed according to approved map and inspected.
PZ Approval:	Final verification that all conditions of approval have been met pertaining to fencing and landscaping.
PI:	Pressurized Irrigation is pressure tested, activated, accepted system by owning jurisdiction.

Please direct any questions regarding this definitions page to Karie Glenn, 898-5500, [glennk@meridiancity.org](mailto:glennk@meridiancity.org)